



- NOTES**
1. ENSURE WIRING IS AS PER QEMM REQUIREMENTS
  2. LOCAL EARTH/EARTH STAKE
  3. EARTH LINK - FOR ALL EARTHS
  4. TERMINALS SHOWN FOR ZEPTO POWER METER, FOR OTHER METERS ENSURE TERMINALS ARE CORRECT
  5. INSERT CORRECT DRAWING REFERENCE DURING DESIGN
  6. WORKS WITH UWSTD-E-DR-9001-31

PFR1	OPTIONS	SETTINGS	PFR2	OPTIONS	SETTINGS
SENSITIVITY (NPS)	5,7,9,11,13,15%		SENSITIVITY (NPS)	5,7,9,11,13,15%	
TIME DELAY		10 SEC	TIME DELAY		10 SEC

<b>A3</b>	0	20.09.23	ISSUED FOR USE							
	REV	DATE	DESCRIPTION OF CHANGE	DRAWN	DESIGNED	REVIEWED	APPROVED	COMPANY		



**Unitywater**  
 STANDARD DRAWINGS  
 CT METERED - MANUAL TRANSFER SWITCH  
 THREE LINE DIAGRAM

PROJECT NUMBER	IFXXXXXX
REVISION DATE	20.09.23
DISCIPLINE CODE	E
DRAWING NO.	UWSTD-E-DR-9002-31